

FOB JAMES, JR.

## ALABAMA DEPARTMENT OF TRANSPORTATION

CONSTRUCTION BUREAU 1409 COLISEUM BOULEVARD MONTGOMERY, ALABAMA 36130-3050

PHONE (334) 242-6208 FAX (334) 264-3727 RW OR

JIMMY BUTTS
TRANSPORTATION DIRECTOR

## CONSTRUCTION INFORMATION MEMORANDUM NUMBER 1-95

DATE:

May 18, 1995

TO:

All Division Engineers

FROM:

N. S. Cauthen

Construction Engineer

RE:

NBIS Bridge Inspections of Bridges Under Construction

All portions of bridges that are constructed under a "Staged" or "Phased" sequence of construction must be inspected in accordance with the requirements of the National Bridge Inspection Standards (NBIS) prior to the placement of traffic on the bridge.

Manther

"Phased" or "Staged" construction is often utilized to allow the completion of a portion of a bridge to carry traffic while the construction of the remainder of the bridge is being completed. This allows the undisrupted flow of traffic by keeping an old adjacent bridge structure (that is being replaced) open to traffic during the construction of the first portion of the bridge.

The first "Phase" or "Stage" of the bridge construction must be inspected, as is done at the completion of bridge construction projects, prior to the shifting of traffic to that newly completed portion of the bridge.

NSC/ams

CC:

Mr. Ray D. Bass

Mr. Mitchell Kilpatrick

Mr. W. F. Conway

**FHWA** 

File